

WORLD TRADE CENTER
COPY 01/91

ENGINEERING PROGRAM MANAGER
WORLD TRADE CENTER
CHIEF ELECTRICAL ENGINEER

1 02/29/99 AS-BID
No. Date Revision Approved

ENGINEERING DEPARTMENT
DESIGN DIVISION

WORLD
TRADE
CENTER

ELECTRICAL
Title

FIRE ALARM SYSTEM
DEVICE UPGRADE
PHASE III
1 WORLD TRADE CENTER
CONTRACT NO. 3

45th FLOOR
STROBE
INSTALLATION AND
REMOVAL PLAN

This drawing subject to conditions in Contract. All
inventions, ideas, designs and methods herein are
reserved to Port Authority and may not be used
without its written consent.

S. FELDSTEIN E. KOTSKI A.S.
Designed by Drawn by Checked by

AUGUST 9, 1999
Date

WTC-061.176 E-045-4
Contract Number Drawing Number

NOTES

1. FOR LEGEND, ABBREVIATIONS, AND GENERAL NOTES, SEE DWG. E-1.
FOR INSTALLATION DETAILS, SEE DWG. E-2. FOR WIRING DIAGRAMS,
SEE DWG. E-3.
2. REPLACE EXISTING STROBE WITH THE SHOWN CANDELA RATED STROBE.
AND REWIRE AS SHOWN. EXISTING BACKBOX AND CONDUIT STUB CAN
BE UTILIZED IF IT IS SIMILAR TO THE TYPICAL STROBE OR COMBINATION
BOX. SEE INSTALLATION DETAIL "B" ON DWG. E-2.
3. ONLY AFTER INSTALLED STROBES ARE TESTED AND OPERATIONAL,
SHALL CONTRACTOR REMOVE EXISTING STROBE IN THE PRESENCE
OF THE ENGINEER. PATCH WALL TO MATCH EXISTING WALL FINISH.
4. SINCE FIRE ALARM CIRCUIT LENGTH IS CRITICAL, ROUTING AND
INSTALLATION OF ALL FIRE ALARM CIRCUITS SHALL BE AS SHOWN
ON DRAWING.
5. DISCONNECT AND ABANDON EXISTING STROBE CIRCUITS IN CEILING.
TAPE ENDS OF ABANDONED CONDUCTORS AND TAG AS ABANDONED.
THIS WORK SHALL BE DONE IN THE PRESENCE OF THE ENGINEER.

STROBE CIRCUIT/LOADING TABLE

STROBE TYPE AND RATING	TYPE	15cd	30cd	75cd	110cd	CURRENT PER CIRCUIT (AMPS.)	CIRCUIT LENGTH (ft.)
QUANTITY OF STROBES PER CIRCUIT	STR-A	5	4	1	1	1.089	344
	STR-B	7	0	3	0	0.938	328
	STR-C	8	2	1	0	0.869	314
	STR-D	6	1	3	0	0.973	437
	STR-E	10	2	0	0	0.830	402
	STR-F	7	2	0	1	0.850	350
	GRAND TOTAL	5.547					2175

